

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>26</u> T <u>23N</u> R <u>5W</u>	<u>5</u>
	S <u>26</u> T <u>23N</u> R <u>5W</u>	<u>6</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on May 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 5 - Rec. Survey -L. 309, P. 329 - P. Case - 1997.
Set Iron.
- 6 - None.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 5 - C-N 1/16 Sec. 26 - FND Capped 1/2" Rebar per Rec. Survey. CL of N-S Rd. is 9' ± E. Fit Standard BLM Procedure Position
- 6 - NE 1/16 Sec. 26 - Set 2" A.C. on 5/8" x 34" Rebar per Standard BLM Procedure. CL of 10' wide dirt road is 86' N and curves SE to 110' ± E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 5 - Replace Cap 1/2" x 18" Rebar w/ 2" A.C. on 5/8" x 34" Rebar.
S88°E 50.00' to 2" A.C. on 5/8" x 34" Rebar w/ Carsonite Guard Post on N 1/16 Line.
N89°W 23.30' to Cap Iron Rod - FND.
N60°E 109.16' to N&T in N. Side 9" W. Birch
N30°W 133.79' to N&T in W. Side 8" W. Pine
- 6 - 2" A.C. on 5/8" x 34" Rebar w/Carsonite Post 1' NW.
N49°W 33.15' to N&T in NE Side 3" R. Maple
N78°E 46.57' to N&T in S. Side 11" R. Pine
S38°E 41.87' to N&T in NE Side 15" R. Pine
S32°W 16.91' to N&T in NW Side 6" R. Maple
N70°E 55.74' to CL. 2" O.D. Iron Pipe in Concrete

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 3/6/1998