

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>24</u> T <u>23</u> N R <u>5</u> W	<u>12</u>
	S <u>26</u> T <u>23</u> N R <u>5</u> W	<u>2</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on March 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

12 - None 2 - None



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

12 - C-S 1/16 Sec. 24 - Set 2" A.C. on 5/8" x 34" Rebar in swamp per Standard BLM Procedure. N-S Cable Wire is 103' ± E. 2 - E 1/16 Sec. 23 & 26 - Set 2" A.C. on 5/8" x 34" Rebar 1' ± N. of Phy C.L. Gaukel Rd. per Standard BLM Procedure. Driveway S. is 37' ± E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

12 - 2" A.C. on 5/8" x 34" Rebar with Carsonite Post 1' NE
 N62°E 23.91' to N&T in NW Side 8" J. Pine
 S75°E 21.19' to N&T in N. Side 6" J. Pine
 N27°W 11.39' to N&T in N. Side 5" J. Pine
 S16°W 66.89' to N&T in NW Side 6" J. Pine 2 - 2" A.C. on 5/8" x 34" Rebar.
 South 33.02' to 2" A.C. on 5/8" x 34" Rebar with Carsonite Guard Post on E 1/16 Line.
 N40°E 44.82' to N&T in NW Side 9" J. Pine
 S20°W 34.16' to N&T in SE Side 10" W. Pine
 S55°W 46.06' to N&T in NW Side 13" W. Pine

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 3/6/1998