

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>5W</u>	<u>J-10</u>
	T <u>23N</u> R <u>5W</u>	<u>J-8</u>
2. Property Controlling in Section	T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on May 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|
| <u>J10</u> - Miss. Co. BK 24, P. 24 & BK21, P. 59 - 1915
Set Post - WPS 40" N62°E 42L.
- Miss Co. BK. 21, P. 118 - Rd. Survey
- Rec. Survey L. 309, P. 329 - P. Case - 1997 | <u>J8</u> - None. |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <u>J10</u> - C1/4 Sec. 26 - Found Capped 3/4" Iron Pipe per Rec. Survey. P. Case and DNR Crew dug in this area but no remains of Old Post or BT was found. Area disturbed by Road Const. P. Case established position per Old County Notes. Fence Line S. is 12' ± E. Monument accepted as the best available evidence of the position of the corner. | <u>J8</u> - C1/4 Sec. 23 - Set 2" A.C. on 5/8" x 34" Rebar w/1' of 4" PVC Pipe w/concrete - Down 0.5' - at the intersection of 1/4 lines. CL. of N-S Rd. is 8' ± E. |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <u>J10</u> - Capped 3/4" Iron Pipe. Add Ring of Stone and Carsonite Post 0.5' NW.
S47°W 38.87' to Set N&T in NW Side 19" R. Pine
N55°W 90.21' to Set N&T in NE Side 14" R. Pine
N24°W 110.73' to Set N&T in SW Side 15" W. Pine
S74°E 32.94' to Set N&T in SW Side 19" R. Pine
N47°E 75.24' to Set N&T in SE Side 10" W. Pine | <u>J8</u> - Monument per part 'B'.
West 33' to Carsonite Post
S20°W 32.19' to Set 1/2" x 30" Rebar
N45°E 35.34' to Set 3/4" x 26" Iron Rod
S73°E 86.30' to N&T in N. Side 4" Ash |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 3/6/1998