

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>5W</u>	<u>K12</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**Register of Deeds Stamp & File Num.**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on March 3 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

K12-GLO-Set 1/4 post- A. Curtis-1852  
 Maple 10" S25°W 12L.  
 Spruce 8" N15°E 20L.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K12- 1/4 cor. common to sec. 35 & 36- No evidence fnd.- Set 4"  
DNR A.C. on 1"x3' galv. iron pipe at single proportional position  
between K11 & K13. Monument accepted as a careful and faithful  
re-establishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K12- 4" A.C. on 1"x3' iron pipe. set Carsonite guard post 1' +/- N.  
 N 3° W 44.21' to N & T in E. side 8" R. Pine scribed 'XBT'  
 S13° E 8.96' to N & T in W. side 13" R. Pine scribed 'XBT'  
 N 68° E 37.27' to N & T in N. side 11" R. Pine scribed 'XBT'  
 N85° W 49.37' to N & T in N. side 10" R. Pine scribed 'XBT'



Signed by Craig W. McVean  
 Surveyor's Michigan License No. 39088

Date 3/6/1998