

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>5W</u>	<u>K10</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____



4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on February 26 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

K10- GLO-Set 1/4 post-A. Curtis-1852  
Hemlock 7" N 50°E 18L., Hemlock 7" S25°W 14L.  
-Miss. Co. Bk.24, P. 64 & Bk. 21, P.58-Fnd. NE GLO 8T  
standing - set new post-1915- Tam. 3" N26°W 11L.  
Birch N67°E 13L.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K10- 1/4 cor. common to Sec. 25 & 26- Dug 8'x8' area looking for post per Co. notes position. Nothing fnd. Set 4" DNR A.C. on 1"x 3' long iron pipe by extending E-W 1/4 line E'ly from J10 and placing mon.at record Co. dist.from J10. Monument accepted as a careful and faithful re-establishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K10- 4" A.C. on 1" pipe-set carsonite guard post 1.5' SE  
N42°W 30.08' to N & T in SW Side 8" R. Pine scribed 'XBT'  
N 2°W 10.97' to N & T in E Side 8" R. Oak scribed "XBT'  
N 82°E 72.77' to N & T in S Side 11" R. Oak scribed "XBT'  
S19°W 48.28' to N & T in E Side 8" R. Maple scribed "XBT'



Signed by Craig W. McVean  
Surveyor's Michigan License No. 39088

Date 3/6/1998