

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Missaukee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>5W</u>	<u>K - 8</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on February, 20 19 97  
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the  
corner points mentioned in lines 1 and 2 above were in conformance with regulations  
and rules therefore as required in the current manual of survey instructions of the  
United States Department of the Interior, Bureau of Land Management or by a  
decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors  
or by a Decree of a Court of Law; established, re-established, monumented,  
recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8 - GLO - Set 1/4 Post - A. Curtis - 1852  
Tamarack 7" N27°E 20L  
W. Pine 6" S06°W 8L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 -1/4 Cor. Common To Sec. 23 & 24-Found 11" Diameter Cedar Post Bottom at intersection of ancient down woven wire fence W & N with single strand from East. Found post at about level of water in swamp. Measure S. 319' ( GLO&M) +/- 15' to S. edge of swamp. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 -Drove 1" X 60" galv. Iron Pipe with 4" Aluminum DNR Cap in to center of cedar post. Set blue carsonite post.  
S05°E 77.54' to set nail and tag in E side 8" R. Pine scribed "XBT"  
N81°W 65.64' to set nail and tag in N side 14" R. Pine scribed "XBT"  
N15°E 83.14' to set nail and tag in E side 10" R. Pine scribed "XBT"  
N74°E 70.29' to set nail and tag in N side 4" R. Pine scribed "XBT"  
S40°E 22.84' to set nail and tag in SW side 2" R. Pine scribed "XBT"



Signed by Craig W. McVean  
Surveyor's Michigan License No. 39088

Date 3/6/1998