

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>5W</u>	<u>I-12</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on February 11 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-12 -GLO-Set 1/4 post-A. Curtis-1852
 Aspen 14" N50°E 25L., Aspen 16" S35°W 30L.
 -Miss. Co. Bk.24, P.63 &Bk.21, P. 60-Subd. Sec. 34-Set
 Cedar Post -1915- Tam. Stub 12" S2°W 26L., Tam. Stub
 10" N11°E 30L.
 -Miss. Co. Bk. 23,P. 55-Sugar 15°S75°W 16L., Hem 9"
 N65°E 21L.
- Geo. Henning-1971-Fence post in corner-Fen. N,S,E&W-Placed
 1/2" iron bar 0.5' S. of cor.- Wit. to 1/2" iron bar, Maple 8"
 SW 29.6', Maple 8" SE 31.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 - 1/4 Cor.common to Sec. 34 & 35- Fnd. base of rotten cedar post fence corner 6"x3.5' long surrounded by boulders and cobbles. GH 1/2" iron was fnd.on S. side. Fence remains N,S,W&E. Fits 1915 survey distances N,S & W. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 - Replace cedar post base with 4" DNR A.C. on 1"x4' long galv. iron pipe in ring of stone. Reset cedar post on NW side below gnd. and 1/2" iron on S side monument as memorials.
 Set blue Carsonite Post 1' NE
 S70°E 177.50' to N & T in N side 10" W. Oak scribed 'XBT'
 N41°W 65.32' to N & T in SW side 6" Maple scribed 'XBT'
 S12°E 52.43' to N & T in W side Twin 4" Maple scribed 'XBT'
 S60°W 94.13' to N & T in NW side 1 4" Maple scribed 'XBT'
 N54°E 40.61' to N & T in SE side 4" Maple scribed 'XBT'



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 3/6/1998