

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>5W</u>	<u>H12</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on MAY 21 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- H-12 - Miss. Co. Surveyor Bk. 24, P. 63- Subdivision of Sec. 34  
Set cedar post- 1915- Tele pole S. 15L.; WPS 10° N 62°E 35L  
- Miss. Co. Sur. Bk. 8, P. 42-same witnesses as Bk. 24-  
dist. N, S & E- 1919  
- Geo. Henning- Place 1/2" iron bar in CL. Road, fences E & W -1971

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-12- C 1/4 Sec 34- Fnd. 6" dia. Cedar post bottom with fence wire to E. and anchor wire to W. at E. side of N-S gravel road. Fits Co. Survey distances N,S, W & E closely. This monument was apparently established by Co. surveyor, E.A. Beuthen in 1915 and is accepted as the best available evidence of the position of the corner.  
**Reference Pt.-** Found G. Henning iron bar at CL of N-S gravel road N 89°23' W 19.10' of H-12. Monument was set without regard to record County survey and is not utilized as H-12 in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-12- Drove 5/8" X 34" rebar with 2" alum. Cap in center of found cedar post. Built ring of stone. Set orange carsonite 1' N.  
East 82.96' to N&T in N. side 5" Spruce  
N44°E 55.06' to fnd. 1/2" rebar  
S3°W 84.20' to N&T in E. side 10" Elm  
N89°W 101.74' to N&T in S side UP



Signed by Craig W. McVean  
Surveyor's Michigan License No. 39088

Date 3/10/1998