

JAN 30 1996  
COMMISSION

#1806

LIBER 300 PAGE 600

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Missaukee Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey	T	<u>23N</u>	R	<u>5W</u>	<u>C-13</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

MISSAUKEE COUNTY MICHIGAN  
 RECORDED DEC 22 1995 2:25 PM  
*Pauline Klare*  
 REGISTER  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2	
3										
4	7		8		9		10		11	
5										
6	18		17		16		15		14	
7										
8	19		20		21		22		23	
9										
10	30		29		28		27		26	
11										
12	31		32		33		34		35	
13										

I, J. Dean Geers, in a field survey on September, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-13) 1837 GLO Section post by John Brink, Deputy Surveyor, Beech 14-N 61° E-7, Sugar 12- N 37 1/2° W-36
- C-13) 1915 Beuthien Survey in Section 32, T23N, R5W; Set new post, no witnesses
- C-13) 1958 MDOT Survey M-55, F 388(2); No Corner shown.
- C-13) 1976 Wilcox LCRC, Liber 1, Page 204; found 1/2" iron rod; N 45° E-98.40'-12" Box Elder, North- 52.40'-P. Pole
- C-13) 1983 Cavanagh Survey, Liber S-2, Page 141; Found 1/2" iron rod, S 23° E-84.6'-T. Pole, N 5° E-52.37'- P. Pole, N 56° E-98.35'-18" Ash
- C-13) 1985 Wilcox Survey, Liber S-2, Page 227; Found 1/2" Iron ; N 70° E-149.20'-P. Pole, N 45° E-98.40'-18" Box Elder, North-52.40'-P. Pole, S 26° E-84.62'-Utility Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-13) Section corner Common to Section 31 and 32, T23N, R5W and Section 5 and 6, T22N, R5W. Found Iron in centerline of East-West Road as recorded in LCRC Liber 1, Page 204. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13) Set 2 1/2" Brass Missaukee County Mon. on existing Iron in Mon. Box  
 N 07° E - 52.40' - P. Pole  
 N 55° E - 98.44' - 16" Box Elder  
 S 24° E - 52.88' - Set Iron  
 S 37° W - 53.09' - Set Iron

Peer Group Reviewed and Approved  
 Date: 11-29-95  
*J. Dean Geers*  
 J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12-22-95  
 Surveyor's Michigan License No. 33977