

MISSISSIPPI
JAN 30 1996

1012

LIBER 300 PAGE 60

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Missaukee Located In: _____ Corner Code # _____
(County)

- 1. Public Land Survey T 23N R 5W I-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 22 1995 2:25

Paula Flare
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2	
3										
4	7		8		9		10		11	
5										
6	18		17		16		15		14	
7										
8	19		20		21		22		23	
9										
10	30		29		28		27		26	
11										
12	31		32		33		34		35	
13										

I, J. Dean Geers, in a field survey on October, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-13) 1837 GLO Section post by John Brink, Deputy Surveyor; Beech 11- N 23° E-10, Beech 16- N 43° W-53
- I-13) 1915 Beuthien Survey in Section 2, T22N, R5W and Section 34, T23N, R5W; Found post by Richardson, set new post at int. of lines, Elm 7-S 1/2° E-2.42
- I-13) County Survey notes page 53; Beech 12-S 60W-27, Hem 16-S 55E-30
- I-13) MDOT ROW Plans; Sec. Corner on Tang at STA 835 + 47.1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-13) Section corner Common to Sections 34 and 35, T23N, R5W and Sections 2 and 3, T22N, R5W. Found 1" Iron ± 6' North of centerline East-West Road. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-13) Set 2 1/2" Brass Missaukee County Mon. on existing Iron in Mon. Box
S 27° E - 42.48 - Set Pk in Center 12" conc. culv.
S 06° W - 75.41 - Power Pole with Tele Riser
North - 37.60 - 8" Poplar
N 45° E - 53.47 - 7" Poplar

Peer Group Reviewed and Approved

Date: 12-6-95
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12-22-95

Surveyor's Michigan License No. 33977