

SURVEY & REMONUMENTATION

JAN 27 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1267

LIBER 318 PAGE 156

For corners in SECTION

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>5W</u>	<u>K12</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED APR. 9 1998 ^{2:15} P.M.

Caryn Flare
REGISTER

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on March 3 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K12-GLO-Set 1/4 post- A. Curtis-1852
Maple 10" S25°W 12L.
Spruce 8" N15°E 20L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K12- 1/4 cor. common to sec. 35 & 36- No evidence fnd.- Set 4"
DNR A.C. on 1"x3' galv. iron pipe at single proportional position between K11 & K13. Monument accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K12- 4" A.C. on 1"x3' iron pipe. set Carsonite guard post 1' +/- N.
N 3° W 44.21' to N & T in E. side 8" R. Pine scribed 'XBT'
S13° E 8.96' to N & T in W. side 13" R. Pine scribed 'XBT'
N 68° E 37.27' to N & T in N. side 11" R. Pine scribed 'XBT'
N85° W 49.37' to N & T in N. side 10" R. Pine scribed 'XBT'

Peer Group Reviewed and Approved

Date: 4/8/98

J. Dean Beers
J. Dean Beers, Missaukee Co. Representative



Signed by Craig W. McVean
Surveyor's Michigan License No. 39088

Date 3/6/1998