

JAN 30 1996

#1014

LIBER 300 PAGE 608

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Missaukee (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>5W</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 22 1995 2:25 PM

Carolyn Klare
REGISTERER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, J. Dean Geers, in a field survey on October, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K-13) 1837 GLO Section post by John Brink, Deputy Surveyor; Birch 4-N55 1/2 E-16, Birch 6-N5W-11
- K-13) Co. Survey Notes: Ash 4-S25W-7, W. Birch 8 -S55E-23.
- K-13) 1915 Beuthien Survey in Section 2, T22N, R5W; Oak 12-N4 1/2E-2.12

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-13) Section corner common to Section 35 and 36, T23N, R5W and Section 2 and 1, T22N, R5W. Reestablished the corner position by single proportion between the SW corner of Section 35 and the SE corner of Section 36, T23N R5W. This corner is accepted as a careful and faithful reestablishment of the positions of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-13) Set 2 1/2" Brass Missaukee County Mon. on 1/2" Iron
N 25° E - 11.30 - 10" W. Pine
N 80° E - 8.33 - 4" Oak
S 05° W - 26.96 - 5" Jack Pine
N 65° W - 18.79 - 24" Oak

Peer Group Reviewed and Approved

Date: 12-6-95
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12-22-95

Surveyor's Michigan License No. 33977