

JAN 30 1996

#1015

LIBER 300 PAGE 608

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Missaukee (County) Located In: Corner Code #

- 1. Public Land Survey T 23N R 5W L-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 22 1995 22

Pauline Klar
REGISTRAR

Register of Deeds Stamp & File Number.

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

I, J. Dean Geers, in a field survey on October, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-13) 1837 GLO Quarter Section post by John Brink, Deputy Surveyor; Maple 8-N73 1/2 E-46, Hemlock 8-N20W-63
- L-13) 1915 Beuthien Survey in Section 1, T22N, R5W; W. Pine Stump 24-S-127
- L-13) MDOT ROW and Construction Plans; No corner shown.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-13) Quarter Section corner common to Section 36, T23N, R5W and Section 1, T22N, R5W; Reestablished the corner position by single proportion between the SW cor. of Section 35, T23N, R5W and the SE corner Section 36, T23N R5W. The corner falls 11' North of the centerline M-55. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13) Set 2 1/2" Brass Missaukee County Mon. on 1/2" Iron in Mon. Box.
S 25° W - 73.61 - 12" White Pine
S 25° E - 78.23 - 7" Poplar
N 35° W - 90.55 - 10" Poplar
N 05° E - 86.43 - 7" Poplar

Peer Group Reviewed and Approved

Date: 12-6-95
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12-22-95

Surveyor's Michigan License No. 33977