

JAN 30 1996

#1016

LIBER 300 PAGE 610

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Missaukee  
(County)

Located In:

Corner Code #

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 22 1995 2:25 PM

*Pauline Flors*  
REGISTER

Register of Deeds Stamp & File Number

1. Public Land Survey	T	23N	R	5W	M-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2	
3										
4	7		8		9		10		11	
5										
6	18		17		16		15		14	
7										
8	19		20		21		22		23	
9										
10	30		29		28		27		26	
11										
12	31		32		33		34		35	
13										

I, J. Dean Geers, in a field survey on October, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-13) 1837 GLO Section post by John Brink, Deputy Surveyor, W Pine 12 -S28E-11, Tamarach 10-S61 1/2W-54
- M-13) 1914 Beuthien Survey in Section 1, T22N, R5W; W.Pine10-S 6 W-20, Pine 10-S77W-245, W Pine10-N29E-70.
- M-13) 1958 MDOT Survey M-55, Proj. F388(2); Boat Spike in 1" Pipe, N16W-105.61-End Fence Post, N42E-89.86-8"Poplar, SSE-61.65-end gate post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-13) Section Corner Common to Section 36, T23N, R5W, Section 31, T23N, R4W, Section 6, T22N, R4W and Section 1, T22N, R5W. Found Iron in mon. box in centerline of road intersection. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-13) Set 2 1/2" brass Missaukee County Mon. on existing Iron in mon. box.  
S 20° E - 58.51 - Set Iron  
S 30° W - 68.44 - 4 Poplar  
S 55° W - 84.52 - 10" Poplar  
N 20° E - 94.58 - Top Center conc. R/W Post

Peer Group Reviewed and Approved

Date: 12-6-95  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12-22-95

Surveyor's Michigan License No. 33977