

NOTATION

#1017

JAN 2 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in  
Missaukee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 23 R 6 Corner Code # B-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

MISSAUKEE COUNTY MICHIGAN

RECORDED JAN 2 1996 1:15 P.M.

*Roslyn Flare*  
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema a field surveyor on August, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-13) 1837 GLO post by John Brink, Deputy Surveyor  
Beech 14"
- E-13) G.S. Gullikson Field book page 47  
Basswood Tree 7, S42 1/2W 85 1/2, Elm 6, S72 1/2W 138.
- B-13) 1898 E.A. Buethien, Co. Surveyor notes Book 33 page 64.  
Basswood 7, S42 1/2W 85 1/2.  
(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-13) South 1/4 corner common to Section 31, T23N, R7W, and Section 6, T22N, R7W.  
Set corner by single proration from E.A. Buethien notes of 1898 and 1914. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-13) Placed Brass Missaukee County Monument with #24617 on a 1/2" iron w/ Monument Box.  
S27°W 77.46 Set Witness Iron  
S22°E 70.61 Set Witness Iron  
N33°E 64.36 Set Witness Iron  
N27°W 70.36 Set Witness Iron

Peer Group Reviewed and Approved

Date: 1-2-96  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema*  
Surveyor's Michigan License No. 24617

Date 12-29-95