

SECTION

1024

JAN 8 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKEE COUNTY MICHIGAN

For corners in Missaukee COMMISSION

RECORDED JAN 2 1996 1:15 P.M.

Angela Klare
REGISTER

(County)	Located In:	Corner Code #
1. Public Land Survey	T 23 R 6	C-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel E. Schripsema in a field survey on August, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-13) 1837 GLO post by John Brink, Deputy Surveyor
Hemlock 10 N68°E 9, Sugar 18 N63°W 14
- C-13) 1898 County Survey Records fieldbook 33 page 64
Stone, Elm 8, N45E 66 ft, Beech 6, N63E 43 ft
- C-13) G.S.Gullikson fieldbook page 47.
Elm 8, N45E 66 ft, Beech 6, N63E 43 ft.
- C-13) 1905 John McBain, Co. Surveyor field book page 66
sleigh shoe
(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-13) Section corner common to Sections 31 and 32

Found empty monument box in centerline M-55, 1.5' West centerline Rd. North, and 4.2' West centerline Rd. South. This corner is accepted as a careful and faithful perpetuation of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13) Placed 1/2" Iron with Brass Missaukee County Monument in existing Mon. Box with #24617.

- *N38°W 63.30 USGS Bench
- *N36°E 95.07 32" Maple
- N20°E 109.16 twin 14" Maple
- S61°E 116.15 46" Maple
- * = Old witness

Peer Group Reviewed and Approved

Date: 1-2-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema*

Date 12-29-95

Surveyor's Michigan License No. 24617