

**SURVEY &
REMONUMENTATION**

JAN 27 1999

LIBER 324 PAGE 1275

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

#1295

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T. <u>23N</u> R. <u>6W</u>	<u>D-1</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Property Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Sec.	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN
RECORDED DEC 28 1998 *1:00 PM*
Paulyn Flare
REGISTER
Register of Deeds Stamp & File Number

I, Daniel E. Schripsema, in a field survey on October 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L	M
1			●									
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- D-1) 1838 John Brink GLO survey, set quarter post section 5; Black Ash 14 N51 1/2W 10, do 13 N50 1/2E 19 1895 Richardson survey; Cedar stake 30" long nearly level with the ground and placing number of large boulders a around it. Stake was about 12 links South of Causeway in soft ground
- 1915 County Survey book page 67, shown but no comment. Witness Elm N47E 51, CFP S1E 49

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-1) Quarter Section Corner common to Section 32, T24N, R6W and Section 5, T23N, R6W, Set 1/2" rerod with Missaukee County Monument by single proration to 1915 survey. Corner falls 1 foot East of edge of a beaver pond
- This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-1) Set Missaukee County Monument on 1/2" rerod
 - N87E 58.22 6" maple
 - S13E 39.53 7" maple
 - S68W 53.13 3" twin maple
 - S89W 73.36 6" elm

Peer Group Reviewed and Approved

Date 10-21-98
[Signature]
_____, Missaukee Co. Representative

Signed by: *[Signature]*

Date 10-22-98

Surveyor's Michigan License No. 24617

