

SURVEY & REMONUMENTATION

JAN 27 1999

LIBER 324 PAGE 1277

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1297

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 23N R 6W	F-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

MISSAUKEE COUNTY MICHIGAN
RECORDED DEC 28 1998 *LPM*
Paulyn Flare
REGISTER
Register of Deeds Stamp & File Number

I, Daniel E. Schripsema, in a field survey on October 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- F-1) 1838 John Brink GLO survey, 11" diameter do is quarter corner of section 4
- 1918 Beuthien (pg.74) - Cedar stake Elm 6 S51 1/4E 47 1/2ft., Maple 5 N14 1/2W 33ft.
- 1992 Carl Roser survey; Restored 1/4 corner common to sec's 4 (23N-6W) & 33 (24N-6W) at fd.stk. bottom shadow, from Beuthien 1918 nbt (6', now 20" elm, dead & down stump, S51E, 47.5') & in line w/ old fn. to S. Ctr.. E-W 2-track (in curve) is 14' south. Drove 5/8" x34" rerod w/rls cap, S00° 52W, 33.00. Set Cedar. Post w/loc. tag 1'E.S.E. 1/4 cor. as restored above is within 2' for calc. Position (S.P. bet sec cor's to E & W: Beuthien notes indicate set it S.P.)
- 1992 L.C.R.C. L.1, pg. 862, set 5/8" rerod with R.L.S. Cap, 10" Ash N80W 33.57, 28" H. Maple Due North 17.84, 13" Ironwood N30E 88.32, 11" H. Maple Clump N35E 15.12, E-W Fence North 34.00, Old Fence Cor. remains. South 34.00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-1) Quarter Section Corner common to Section 4, T23N, R6W and Section 33, T24N, R6W Found 5/8" rerod with R.L.S. Cap - 14' N. Centerline 2track
- This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-1) Set Missaukee County Monument on existing iron
- | | | |
|--------------------|-------|-------|
| 12" Ash | N80W | 33.57 |
| 28" H. Maple Due | North | 17.84 |
| 16" Ironwood | N30E | 88.32 |
| 12" H. Maple Clump | N35E | 15.12 |
| 5/8" Iron & Cap | South | 33.00 |

Peer Group Reviewed and Approved
Date: 10-21-98
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema*

Date 12-22-98

Surveyor's Michigan License No. 24617

