

JAN 30 1996

1027

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKEE COUNTY MICHIGAN

For corners in
Missaukee

RECORDED JAN 2 1996 1:15 P.M.

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23</u> R <u>6</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, a field surveyor on August, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-13) 1837 GLO post by John Brink, Deputy Surveyor Ironwood 10"
- F-13) 1917 Beuthien Notes: Fieldbook #9, pages 90-91
- F-13) 1975 Wilcox LCRC, Liber-page 191: Set boat spike by single proportion
- F-13) 1975 Wilcox survey, Liber S-1, page 241: Set bolt spike in centerline North and South fenceline
- F-13) 1976 Wilcox survey, Liber S-1, page 253: Found bolt spike
- F-13) 1977 Wilcox survey, Liber S-1, page 331: Found boat spike
- F-13) MDOT M-55 file #57-R-1&2, Control Sec. 57022, sheets 18-19: corner is not indicated

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-13) South 1/4 corner common to Section 33

Found bolt spike in centerline M-55, 10' East of drive North and field drive South. This corner is accepted as a careful and faithful reestablishment of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-13) Replaced bolt spike with 1/2" Iron with Brass Missaukee County Monument with #24617 and Monument Box.

S41°E	198.96	P.Pole
S71°W	178.23	P.Pole
S06°E	52.02	Set 1/2" Iron @ cable marker post
N51°W	139.58	32" Maple

Peer Group Reviewed and Approved

Date: 1-2-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema Date 12-29-95
Surveyor's Michigan License No. 24617