

RECEIVED  
JAN 13 1996

#1028

JAN 8 0 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970 MISSAUKEE COUNTY MICHIGAN

For corners in  
Missaukee  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 23 R 6 G-13
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

RECORDED JAN 2 1996 1:15 P

*Paula Klor*  
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Daniel E. Schripsema a field survey on August, 19    , do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- G-13) 1837 GLO post by John Brink, Deputy Surveyor  
Lynn 11 N13°E 22
- G-13) Beuthien Notes, Fieldbook #9
- G-13) 1975 Wilcox LCRC, Liber-page 191: Found Mon. Box
- G-13) 1975 Wilcox survey, Liber S-1, page 241: Found 1/2" rod in Mon. Box
- G-13) 1993 Schripsema survey, Liber S-3, page 262: Found 1/2" pipe/Mon. Box
- G-13) 1993 Schripsema survey, Liber S-3, page 264: Found 1/2" pipe/Mon. Box
- G-13) MDOT M-55 file #57-R-1 & 57-R-2, Control Sec. 57022, sheets 18-19: corner is not indicated

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-13) Section corner common to Sections 33 and 34
- Found 1/2" Iron in Monument Box in centerline of M-55 and 5' West of centerline of Rd. to South and field drive to North. This corner is accepted as a careful and faithful perpetuation to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13) Placed Brass Missaukee County Monument on existing corner with #24617
- |       |       |                        |
|-------|-------|------------------------|
| N10°W | 72.53 | 9" Elm                 |
| N47°W | 85.79 | 18" Elm                |
| S37°W | 76.61 | Fence Post             |
| N15°W | 44.80 | SW cor. conc. Headwall |
| N25°W | 47.40 | SE cor. conc. Headwall |

Peer Group Reviewed and Approved

Date: 1-2-96  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema*

Date 12-29-95

Surveyor's Michigan License No. 24617