

SURVEY & REMONUMENTATION

JAN 27 1999

LIBER 324 PAGE 1279

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1299

SECTION

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>6W</u>	<u>H-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN
RECORDED DEC 28 1998 ¹⁰² *LPM*
Paulyn Klare
REGISTER
Register of Deeds Stamp & File Number

I, Daniel E. Schripsema, in a field survey on October 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- H-1) 1838 John Brink GLO survey, set quarter post section 3: Hemlock 11 N56 1/2W 25, do 11 N78 1/2E 17
- 1992 Carl Roser survey; Reestablished N 1/4 Corner of Section 3 midway & on line between section corners 1/2 mile E & W. Southerly edge of spruce swamp is 176' +/- 15' North. Center of trail (course N50W) is approx. 760' North. Set 3/4" Pipe & DNR Monument.
- 1992 L.C.R.C. L.1, pg. 860; set 3/4" Pipe with D.N.R. Monument, 9" Cedar N70E 25.1, 4" Maple S65E 46.5, 5" Maple S35E 20.9, 8" Balsam S05W 15.0, 6" Maple N80W 3.6.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-1) Quarter Section Corner common to Section 3, T23N, R6W and Section 34, T24N, R6W Found 3/4" Pipe with D.N.R. Monument & treated 4" Pine Post

This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-1) Found 3/4 Pipe & D.N.R. Monument
- 9" Cedar N70E 25.1
- 4" Maple S65E 46.5
- 5" Maple S35E 20.9
- 8" Balsam S05W 15.0
- 6" Maple N80W 3.6

Peer Group Reviewed and Approved
Date: 10-21-98
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____ Date 12-22-98

Surveyor's Michigan License No. 24617

