

JAN 30 1996

#999

LIBER 300 PAGE 59

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Missaukee

(County)

Located In:

Corner Code #

1. Public Land Survey	T	23N	R	06W	H-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 22 1995 2:25 P

Paulyn Klare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

J. Dean Geers, in a field survey on September 8, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-13) 1839 GLO Quarter Section post by John Brink, Deputy Surveyor; Ironwood 10" dia.; no witnesses
- H-13) 1898 Richardson Survey in Section 3, T22N, R6W; Drove Stake, No Bearings.
- H-13) 1906 McBain Survey in Section 34, T23N, R6W; Corner was used, no witnesses.
- H-13) 1958 MDOT Survey M-55, F388(2) Part 2: No corner shown.
- H-13) 1972 L. Cavanagh LCRC, L1, Pg 55; reestablished corner in accordance with long existing property lines 1/2" x 18" steel bar, corner FP - North-50.0, tele pole - S15E-76.3
- H-13) 1993 DNR Survey, project no. 26-93394; Fd strong dip in B-top road, did not dig out this survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-13) Quarter Section corner Common to Section 34, T23N, R6W and Section 3, T22N, R6W. Found 1/2" Iron in centerline East-West Road and on fence line to North as recorded in LCRC, Liber 1, Page 55. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-13) Set 2 1/2" Brass Missaukee County Mon. on existing 1/2" Iron in Mon. Box
N42E - 62.16 - set iron
S23E - 72.73 - set iron
S36W - 96.75 - 8" Aspen
N02E - 51.10 - 4x6 post

Peer Group Reviewed and Approved

Date: 11-29-95

J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *J. Dean Geers* Date 12-22-95

Surveyor's Michigan License No. 33977