

SURVEY & REMONUMENTATION

JAN 27 1999

LIBER 324 PAGE 1280

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1300

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 23N R 6W	I-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 28 1998 1:50 PM

Roslyn Klare
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on October 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-1) 1838 John Brink GLO survey, set corner post common to sections 2 & 3; Beech 8 N53 1/2W 49, Hemlock 11 N44E 26
- 1992 Carl Roser survey; Reestablished NE Cor Sec 3 midway & online between sec corners 1 mile E & W. Ctr of N-S trail is 16' West.
- 1992 L.C.R.C. L-1, pg.859, set 3/4" Pipe with D.N.R. Monument, 8" & 7" B. Cherry N75W 31.1, 6" Balsam N25E 36.8, 6" B. Cherry S75E 18.0, 4" B. Cherry S15E 36.0

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-1) Section Corner common to Sections 2 & 3, T23N, R6W and Sections 34 & 35, T24N, R6W. Found 3/4" Pipe with D.N.R. Monument

This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-1) Found 3/4" Pipe with D.N.R. Monument

6" & 7" B. Cherry	N75W	31.09
7" Balsam	N25E	37.18
8" B. Cherry	S75E	18.26
5" B. Cherry	S15E	36.74

Peer Group Reviewed and Approved

Date: 12-22-98
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by _____

Date 12-22-98

Surveyor's Michigan License No. 24617

