

SURVEY & REMONUMENTATION

JAN 27 1999

LIBER 324 PAGE 1282

1302

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Missaukee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 23N R. 6W	L-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 28 1998 1:00 PM

Roslyn Florie
REGISTER

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel F. Schripsema, in a field survey on October 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

- L-1) 1838 John Brink GLO survey, set quarter post section 1; Sugar 8 N60W 19, Beech 8 N66E 19 1909 Beuthien Book pg. 64 - Set new stake from Remains of old witness trees (Found another stake east of old RR Grade
- 1992 Carl Roser survey; Restored South 1/4 Corner of Section 36 per prior surveys of record by RLS's: Geo. Henning (1967), Gene Ostling (1968), and Larry Cavanagh. Copies of these surveys in our survey file. Line of newer cedar posts w/ 1 strand barbed wire, running Northerly is 20' East. Old E-W barb wire fence is 4' South.
- 1992 L.C.R.C. L-1, pg.856, set 3/4" Pipe with D.N.R. Monument, 3" Balsam N65W 1.2, 3" Beech S35E 6.0, 13" Sugar Maple South 30.0, 8" Sugar Maple S57W 23.1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-1) Quarter Section Corner common to Section 1, T23N, R6W and Section 36, T24N, R6W. Found 3/4" Pipe with D.N.R. Monument - 20' W. of Fe. N. & 4' N. of E&W Fe.

This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-1) Found 3/4" Pipe with D.N.R. Monument

4" Balsam	N65W 1.36 Set Nail
5" Beech	S35E 6.28 Set Nail
14" Sugar Maple	South 30.97 Set Nail
8" Sugar Maple	S57W 23.51 Set Nail

Peer Group Reviewed and Approved

Date: 10-21-98

J. Dean Beers, Missaukee Co. Representative

Signed by *Daniel F. Schripsema* Date 12-22-98

Surveyor's Michigan License No. 24617

