

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
MISSAUKEE

Located In: \_\_\_\_\_ Corner Code ~~##~~

- |                                       |   |     |   |    |          |
|---------------------------------------|---|-----|---|----|----------|
| 1. Public Land Survey                 | T | 23N | R | 7W | K-8, K-9 |
|                                       | T |     | R |    | L-9, M-9 |
|                                       | T |     | R |    |          |
|                                       | T |     | R |    |          |
| 2. Property Controlling in Section    | S |     | T | R  |          |
|                                       | S |     | T | R  |          |
| 3. Miscellaneous Property in Sec.     | S |     | T | R  |          |
|                                       | S |     | T | R  |          |
| 4. Lot No. _____, Recorded Plat _____ |   |     |   |    |          |
| 5. Private Claims _____               |   |     |   |    |          |

Register of Deeds Stamp & File Number

I, CARL KIISKILA, in a field survey on APRIL 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

K-8	K-9	L-9
(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)		B) CONT- THIS FALLS IN FLOODED AREA AND STREAM WAS FROZEN OVER AND HARD TO TELL WHERE EDGES OF STREAM WERE.



**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-8	K-9	L-9	M-9
REESTABLISHED THE W 1/4 COR SEC 24 MIDWAY AND ONLINE BETWEEN FOUND SW COR AND REESTABLISHED NW COR. OF SEC. 24. SOUTH EDGE OF 10' WIDE STREAM IS 138' N. GLO CALLS FOR 2 CHAINS (132') NORTH TO STREAM.	FOUND AND ACCEPTED A 1/2" REROD FOR THE COR COMMON TO SEC 23, 24, 25 & 26. OLD CEDAR POST FENCE, WITH SMOOTH WIRE, TO WEST IS 22' ± SOUTH.	REESTAB S 1/4 COR OF S-24, MIDWAY AND ON LINE BETWEEN FD SE & SW COR'S OF S-24. FITS FD CTR OF S-25 AS USED FOR PLATS AND OTHER SUR'S IN S-25. COR ALSO FITS US STREAM TIES TO E & W VERY REASONABLE; US=60 LKS (40') W. TO STREAM, WE MEAS 34' ± & US=4.6 CHS (304') W. OF EAST EDGE OF STREAM TO 1/4 COR. WE MEAS 318' ± 20' TO W. EDGE OF STREAM. -CONT ABOVE-	FD STEEL FN POST FOR SE COR OF SEC 24 AS SET BY P.S. M. McCLUNG (BY PRORATING TWP LINE) IN 1974.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-8	K-9	L-9	M-9
SET 1" x 10' GALV PIPE W/ALUM DNR CAP, SET CARSONITE POST AND CEDAR POST. 16" CEDAR N30°W 163.23' 11" DEAD CEDAR N55°E 63.76' 8" TAMARACK S50°W 83.84'	FOUND 1/2" REROD 6' W OF CTR OF ROAD TO S. & AT N. EDGE OF ROAD TO WEST. P. POLE S54°W 71.18' 22" R. PINE N16°W 43.19' FLAG POLE N61°E 26.78' 14" R. PINE S41°E 56.23'	SET 1" x 10' GALV. PIPE W/ALUM. DNR CAP AND CARSONITE POST. 6" W.PINE NORTH 141.55' 5" CEDAR S05°W 28.84' E. EDGE OF STREAM WEST 34' ± W'LY EDGE STREAM EAST 318' ± N. EDGE STREAM SOUTH 99' 2" BALSAM S65°W 113.05'	FD STEEL FENCE POST, 12" TALL, SET CARSONITE POST. 3" BALSAM S34°W 18.56 2" SPRUCE N40°E 12.18' #CEDAR(DEAD) S58°W 28.12' #12" CEDAR(DEAD) N65°W 36.78' #10" CEDAR(DEAD) N50°E 7.15'

Signed by Carl T. Kiiskila Date 3-28-97 \*M. McCLUNG WIT.

Surveyor's Michigan License No. 33981