

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
NISSAUKEE
 (County)

Located In: _____ Corner Code ~~##~~

- | | | |
|------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T 23N R 7W | L-7, M-6, M-7 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S 13 T _____ R _____ | 12 |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, CARL KIISKILA, in a field survey on APRIL 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(NO EVIDENCE OF G.L.C. CORNER, D.T.G. LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.C. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7	M-6	M-7	12
REESTABLISHED THE S 1/4 COR SEC 13 MIDWAY AND ON LINE BETWEEN FOUND SE COR AND REESTABLISHED SW COR OF SEC 13. COR FALLS IN CEDAR SWAMP, NWLY EDGE OF SWP IS 73' ± 15' N.	ACCEPTED FD. OLD PIPE FOR E1/4 COR OF SEC. 13. PIPE FD. AND ACCEPTED BY P.S. PHIL CASE IN 1991.	FD REROD FOR SE COR OF S-13 AS SET BY P.S. PHIL CASE IN 1991 (P.CASE SET REROD ON TWP. LINE & PROPORTIONATE DIST BETWEEN FD W1/4 COR S-18, T23N-R6W AND FD NW COR S-30, T23N-R6W). TRAIL INTR. IS 150' EAST.	ESTABLISHED THE NW COR OF THE SW 1/4 OF THE SE 1/4 OF SEC 13 PER STD BLM INSTRUCTIONS. SLY EDGE OF CHIMNEY IS 1.3' N. WLY EDGE OF CABIN FOUNDATION (CONC BLK) IS 0.8' E. CTR OLD ABANDONED E-W RR GRADE IS DUE SOUTH 93'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7	M-6	M-7	12
SET 1" X 84" GALV PIPE W/ALUM DNR CAP, SET CARSONITE POST.	FD 1 1/2" PIPE & SET CARSONITE POST.	FD CAPPED 1/2" REROD & SET CARSONITE POST.	SET 5/8" X 34" REROD W/PS CAP & CARSONITE POST.
6" CEDAR S65°W 3.12'	5" BALSAM S54°E 27.90'	1 1/2" W. PINE N12°W 16.70'	9" W. BIRCH S20°E 20.67'
4" CEDAR N35°W 8.19'	8" MAPLE N83°W 35.45'	1 1/2" OAK S06°W 11.18'	6" B. CHERRY S50°W 40.20'
12" MAPLE N45°E 18.53'	10" MAPLE NORTH 13.95'	1 1/2" OAK S53°W 32.35'	12" R. OAK N58°W 33.63'
10" CEDAR S70°E 11.72'	1 1/2" POPLAR S40°E 15.65'	1 1/2" W. BIRCH S64°W 25.08'	
	1 1/2" MAPLE S50°W 27.15'		

1 P. CASE #30079 WITNESSES

1 P. CASE #30079 WITNESSES

Signed by Carl T Kiiskila Date 3-28-97

Surveyor's Michigan License No. 33981