

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MISSAUKEE
 (County)

Located In: _____ Corner Code #/

- | | | | | | |
|---------------------------------------|---|-----|---|----|---------------|
| 1. Public Land Survey | T | 23N | R | 7W | K-3, L-3, M-3 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | 1 | T | R | 15 |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3											●	●	●
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL KIISKILA, in a field survey on JUNE 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(NO EVIDENCE OF G.L.C. CORNER, B.T.G., LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.C. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 REESTABLISHED THE SE COR OF SEC. 2 ON LINE AND DOUBLE DIST ACROSS FD S1/4 COR OF SEC 2 AND FD E1/8 ON SOUTH LINE OF SEC 2. CENTER OF E-W B.TOP ROAD IS 8.5' SOUTH. CTR. OF DIRT ROAD TO SOUTH IS WEST 4.5'.	L-3 REESTABLISHED S1/4 COR OF SEC. 1 AT PRORATED DISTANCE TO E.A. BEUTHEIN 1911 SURVEY OF SEC. 1, BETWEEN REESTABLISHED SW COR S-1 AND FD. SE COR S-1 AND IN CTR. OF E-W B.TOP RD. COR FALLS IN LINE W/OLD FENCE REMAINS TO N & SOUTH ± 4'.	M-3 FOUND AND ACCEPTED A 1/2" REROD AS SET BY P.S. L.CAVANAGH FOR THE SE COR OF SEC 1. SEE PAGE 83 L.C.R.C. FOR ADDITIONAL INFORMATION. COR IS 3.7' SOUTH OF CTR. OF CUTCHEON (E-W B.TOP) RD AND IN LINE W/CTR. OF FORWARD (SAND RD TO N, OLD ABANDONED RD S) ROAD. ROW FENCES TO SOUTH ARE 27'± E & 33'± W.	15 ESTABLISHED THE SW COR OF THE SE1/4 OF THE SW1/4 OF SEC 1 PER STANDARD BLK INSTRUCTIONS.
---	---	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 SET 5/8" X 16" REROD W/CAP IN BLACKTOP ROAD. 6x6 WOOD SIGN POST N60°W 35.48' 4x4 WOOD POST, PHONE RISER SUPPORT N60°E 56.06' 4x4 WOOD POST, PHONE RISER SUPPORT S45°E 65.27' 4x4 WOOD POST, PHONE RISER SUPPORT S45°W 55.74'	L-3 SET 5/8" X 32" REROD W/CAP. SET CARSONITE POST NORTH 33' 8" CEDAR S34°E 47.59' 10" MAPLE S04°W 42.83' 6" CEDAR S58°W 61.96' POWER POLE N57°W 75.89'	M-3 FD 1/2" REROD. CHISEL HOLE TOP CONC. CULVERT N53°E 43.68' 7" CEDAR N10°W 47.85' 22" W. PINE N77°E 99.35' S. END CONC. CULVERT CHISELED HOLE S43°E 44.32'	15 SET 5/8" X 16" REROD W/CAP. SET CARSONITE POST NORTH 33' POWER POLE N49°W 61.64' 6" CEDAR S58°W 53.18' 12" Y. BIRCH S14°W 46.61' 10" MAPLE S27°E 54.12' CTR RD SOUTH 0.8'
--	---	---	---

† L. CAVANAGH WITNESS.

Signed by Carl T. Kiiskila Date 3-28-97

Surveyor's Michigan License No. 33981