

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MISSAUKEE

	(County)	Located In:	Corner Code #
1. Public Land Survey		T <u>23N</u> R <u>7W</u>	<u>M-2</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S <u>1</u>	T _____ R _____	<u>6,7,9</u>
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL KIISKILA, in a field survey on JUNE 8, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(NO EVIDENCE OF G.L.C. CORNER, B.M., LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.C. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>M-2</u>	<u>6</u>	<u>7</u>	<u>9</u>
FOUND AND ACCEPTED A 1/2" REROD AS SET BY P.S. L. CAVANAGH FOR THE E1/4 COR SEC 1. SEE PAGE 83 L.C.R.C. FOR ADDITIONAL INFORMATION. CTR N-S TRAIL WEST 2'. R.R. TIE POST S70 E 8.0'.	ESTABLISHED THE NW COR OF THE SE1/4 OF THE NE1/4 SEC 1 PER STD BLM INSTRUCTIONS. E-W B-WIRE FENCE IS 24' 8'.	ESTABLISHED NE CORNER OF THE SE1/4 OF NE1/4 SEC 1 PER STD B.L.M. INSTRUCTIONS.	ESTABLISHED SW COR OF THE SE1/4 OF THE NE1/4 SEC 1 PER STD B.L.M. INSTRUCTIONS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>M-2</u>	<u>6</u>	<u>7</u>	<u>9</u>
FD 1/2" X 17" REROD, 1" TRI W. BIRCH S14°W 58.37', 10" TRI MAPLE S11°E 45.66', 1" FD REROD (#17614) EAST 33.00', 5" TW MAPLE N58°E 27.22', 4" CHERRY N40°W 41.02', SET CARSONITE POST WEST 33'	SET 5/8" X 32" REROD W/CAP AND CARSONITE POST, 3" MAPLE N64°E 19.87', 4" Y. BIRCH S21°E 15.03', 6" MAPLE S24°W 19.07', 2" MAPLE N37°W 5.05'	SET 5/8" X 32" REROD W/CAP ON WEST SIDE N-S TRAIL RD. FENCE LINE EXTENDED E. NORTH 7', 4" CHERRY N81°W 73.9', 10"-20" MAPLE CLUMP OF 4 S50°W 89.5', 7" POPLAR S15°W 99.3'	SET 5/8" X 32" REROD W/CAP, 4" BEECH S06°W 18.1', 4"-14" TRI MAPLE N55°W 6.4', 22" TW BEECH N28°E 7.8', 24" BEECH S83°E 19.9'

#L.CAVANAGH WIT. #17614 9-6-72

Signed by Carl T. Kiiskila Date 3-28-97

Surveyor's Michigan License No. 33981