

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MISSAUKEE Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T	<u>23M</u>	R	<u>7W</u>	<u>1-1</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	<u>2</u>	T	_____	<u>3</u>
	S	<u>3</u>	T	_____	<u>9</u>
3. Miscellaneous Property In Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on MAY 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1-1

3

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-1

3

9

FD 3/4" PIPE FOR NW COR S-2, AS FD & RECORDED IN 1981 DEPT. SURVEY IN T24N - R7W. COR COMM TO SEC'S 2 & 3, T23N - R7W AND SEC'S 34 & 35, T24N - R7W. COR IS IN CTR OF N-S ROAD, CTR OF E-W ROAD IS 2' SOUTH.

ESTABLISHED THE SW COR OF THE FRL NW 1/4 OF FRL NW 1/4 OF SEC-2, PER STANDARD BLM INSTRUCTIONS.

FD 3 HORSESHOES & WOODEN POST 16" DEEP IN E-W ROAD FOR NW COR OF NE 1/4 OF SE 1/4 OF SEC-3, RAISED W/ 5/8" X 32" REROD. OLD FENCE TO N & S IS 22' WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-1

3

9

FOUND DNR COR OF RECORD, 3/4" PIPE.
 12" R. PINE S47°E 63.20'
 9P.P. STUB S64°W 40.49'
 13" R. PINE N25°W 77.27'
 14" MAPLE N52°E 73.92'
 9FD. CEDAR POST W/LOCATION TAG S45°E 47'

SET 5/8" X 32" CAPPED REROD.
 10" R. PINE N68°E 50.73'
 P. POLE S79°E 36.34'
 10" TWN MAPLE S46°E 48.04'
 8" BEECH N41°W 51.45'
 CTR N-S RD IS EAST 1'
 SET CARSONITE POST EAST 33'

FD THREE HORSESHOES (DIFFERENT SIZES) & WOODEN POST. SET 5/8" X 32" CAPPED REROD.
 10" ASH S18°E 21.88'
 7" W. BIRCH S30°W 27.70'
 12" HENLOCK N54°E 49.13'
 7" MAPLE N12°W 33.55'
 CTR E-W RD IS NORTH 2'.
 SET CARSONITE POST SOUTH 33'.

9 = 1981 DNR WIT.

Signed by Carl T. Kiiskila

Date 4-10-97

Surveyor's Michigan License No. 33981