

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|----------------------------|---------------|
| <u>MISSAUKEE</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>23N</u> R <u>7W</u> | <u>F-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>9</u> T _____ R _____ | <u>5</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on JANUARY 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | ● | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
 F-3 5

U.S. G.L.D. SET QUARTER SECTION POST; BEECH 12 N28°W 27 LINKS, SUGAR 7 S30°W 8 LINKS.
 OLD NOTES CO RD COMM, BOOK 8; 1/4S - 4 & 9 - IRON POST & STONE - THIS WAS SET MANY YEARS AGO BY RICHARDSON; F POST S24 1/2°E 85, WPS 16 N55°W 73.
 J. RAY P.S. 825869 CERT OF SURVEY'S L.S-2 P.504, L.S-3 P.83 & L.267 P.1460; FD 1 3/4"x 1/16" METAL STRAP; S72°W 36.82' TELE. POLE, N67°W 40.98' 30" MAPLE, N20°E 121.72' POLE, N52°E 63.51'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| | |
|--|---|
| F-3 | 5 |
| FOUND 1 3/4" METAL STRAP PER J.RAY CERT. OF SURVEY'S. CORNER IS 1.5' WEST OF BITROAD INTER. N-S-E. | FOUND REBAR PER RECORD SURVEYS BY J. RAY, PS 825869. FOUND IRON IS 0.04' NORTH AND 0.05' EAST OF TRUE CALC. POSITION. |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 F-3 5

| | |
|--|---|
| FOUND 1 3/4"x 1/16" METAL STRAP. WE BROKE OFF & SET CAPPED 5/8"x 3/4" REBAR @ TRUE. N66°W 40.98' TO SET NAIL & TAG IN N SIDE 36" MAPLE. S32°W 61.68' TO SET NAIL & TAG IN NW SIDE 5" R.PINE. N44°E 77.35' TO SET N & T IN NW SIDE 8" R.PINE. S33°E 84.57' TO N & T IN SW SIDE 5" W.PINE. | FOUND CAPPED 1/2" REBAR IN CTR ROAD. S88°20'E 33.01 TO CAPPED 5/8"x 3/4" REBAR AND CARSONITE POST. S62°W 39.62' TO N & T IN S SIDE 3" R.PINE. S35°E 66.50' TO N & T IN SW SIDE 12" W.PINE. N40°E 61.51' TO N & T IN SE SIDE TRIPLE 12" BEECH. |
|--|---|

† = J.RAY MIT.

Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 5-16-97