

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MISSAUKEE

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-----------------|
| 1. Public Land Survey | T <u>23N</u> R <u>7W</u> | <u>E-5, F-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling In Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property In Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on JANUARY 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|--|
| <p>E-5
 U.S. G.L.O. SET POST CORNER SECTIONS 8-9-16-17; BEECH 11 N88°E 27 LINKS, BEECH 8 N68°W 23 LINKS, BALSAM 7 S19 1/4°W 29 LINKS.
 E.A. BEAUTHINE, 1892-1914 SURVEY PERPETUATED CORNER & NOTED OB OK; NB WPS 12 S20°W 47 1/2, CHERRY 4 N36 1/2°W 26.
 K.J. OSTLING, 1962 CONSERVATION DEPT. SURVEY FD 1" BOLT SURROUNDED BY ROCKS, FD STP OF 4" CHERRY NBT, IN LINE W/FN TO NORTH; 12" TW.MAPLE N16°E 56.5', 16" R.OAK S68 1/2°W 12.8',</p> | <p>F-4
 J.RAY, PS #25869 SET 1/2" REROD, PER CERT. OF SURVEY L. S-2, P.504 DATED SEPT. 24, 1981; S63°W 38.14' U.G. TELE POST, N75°E 31.62' TELE. POLE, S40°E 99.22' POWER POLE, N88°W 61.37' POST.</p> |
|---|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|--|---|
| <p>E-5
 FD BOLT AND WIT PER K.OSTLING 1962 DEPT. SURVEY. CTR. OF E-W SAND ROAD IS 5' SOUTH, CTR OF 2-TRACK NORTH IS 10'+/- WEST.</p> | <p>F-4
 ACCEPTED J.RAY 1/2" REROD. CORNER IS IN CTR OF N-S GRAVEL ROAD.</p> |
|--|---|



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p>E-5
 FD BOL, REPLACED WITH 1"x 36" GALV. PIPE W/4" ALUMN DNR CAP WITH 6"x 10" CONC CYLINDER UNDER CAP.
 DROVE BLUE CARSONITE POST W/LDC TAG NORTH 20'
 815" TW.MAPLE N16°E 56.46' (DROVE NAIL & TAG SE SIDE)
 822" R.OAK S69°W 123.76' (DROVE NAIL & TAG)
 8" W.PINE N75°E 108.62' (DROVE NAIL & TAG S SIDE)
 12" R.OAK S55°E 58.10' (DROVE NAIL & TAG NE SIDE)</p> | <p>F-4
 FD 1/2" REROD, DROVE 1"x 14" GALV. PIPE W/PS CAP.
 DROVE 5/8"x 34" REROD W/PS CAP & BLUE CARSONITE POST W/LDC TAG S89°17'E 33.00'
 9" J.PINE N63°E 56.30' (DROVE SPIKE & TAG NW SIDE)
 POWER POLE S40°E 97.26' (DROVE PK & TAG SW SIDE)
 11" MAPLE S72°W 52.25' (DROVE SPIKE & TAG S SIDE)
 U.G. TEL POST S58°W 38.12</p> |
|--|---|

† = K.OSTLING 1962 WIT.

† = PS J.RAY 1981 WIT.

Signed by Carl T. Kiiskila
 Surveyor's Michigan License No. 33981

Date 5-16-97