

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MISSAUKEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>7W</u>	<u>E-4</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>9</u> T <u> </u> R <u> </u>	<u>B</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T KIISKILA, in a field survey on JANUARY 8, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8	●	9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 E-4 B

U.S. G.L.O. SET QUARTER SECTION POST; NOR PINE 13 S40°W 16 LINKS, BEECH 12 N20 1/4°E 19 LINKS.
 E.A. BEUTHIEN, 1914: 1/4 S SET BY CAVANAGH; MPS 28 N32°W 41, MPS 28 N35 1/2°W 95.
 J. RAY, PS825869, 1981 CERT. OF SURVEY: FD OLD 3" HUB, SET 1/2" IRON; N55°E 9.34' 6" POPLAR, S45°E 20.98' 5" POPLAR, S55°W 27.48' 5" POPLAR, N28°W 26.98' 24" PINE STP, N5°W 44.75' CLUMP(5) 6" MAPLES.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 E-4 B

FOUND 1/2" IRON PER J. RAY 1981 CERT. OF SURVEY DATA AND ONE E.A. BEUTHIEN PINE STP WIT. OLD FENCE REMAINS (B/WIRE & SOME CEDAR POSTS) TO E-W-S. CTR OF TRAIL ROAD NE'LY & S'LY IS S45 E +/- 63'.	ESTABLISHED NE COR OF NW1/4 OF SW1/4 OF S-9 PER STANDARD BLM INSTRUCTIONS. OLD E-W FENCE REMAINS (B/WIRE ON CEDAR POSTS MOSTLY ON GROUND) IS SOUTH 17' +/- 2'.
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-4 B

REPLACED FD 1/2"x 24" REROD W/PS CAP W/1"x 36" GALV. PIPE W/4" ALUMN DNR CAP & SET BLUE CARSONITE POST.	DROVE 5/8"x 34" REROD W/PS CAP & SET BLUE CARSONITE POST W/LOC TAG.
15" R. OAK N33°E 66.35' (DROVE SPIKE & TAG SE SIDE)	6" W. PINE N25°E 27.45' (DROVE NAIL & TAG E SIDE)
1 24"W. PINE STP N33°W 26.98' (DROVE 3/8"x 8" SPIKE SE OF CTR)	FD 1 1/4" WELL SCREEN OVER 1/2" REROD S85°43'E 20.00'
5" MAPLE S77°W 18.78' (DROVE SPIKE & TAG N SIDE)	18" R. PINE S05°W 37.50' (DROVE NAIL & TAG N SIDE)
5" TW. R. PINE S55°E 80.03' (DROVE SPIKE & TAG NE SIDE)	16" R. PINE S60°W 21.63' (DROVE NAIL & TAG N SIDE)
5" R. PINE N80°E 127.85' (DROVE SPIKE & TAG N SIDE)	

Signed by Carl T Kiiskila
 Surveyor's Michigan License No. 33981

Date 5-16-97