

JAN 30 1996

# 1029

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKEE COUNTY MICHIGAN

For corners in

Missaukee  
(County)

Located In:

Corner Code -#

RECORDED JAN 2 1996 1:15 P.M.

*Barbara Klare*  
REGISTER

- 1. Public Land Survey T 23 R 7 A-1
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema a field surveyor on August, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- A-1) 1838 GLO
  - A-1) 1907 Richarson FB #14 page 71, Cedar Stake
  - A-1) 1967 MDOT Page Fd. 3/4" pipe
  - A-1) 1967 MDOT Page witness record Fd. 3/4" pipe
  - A-1) MDOT Control Sec. 57013, file #57-R-1, Sheet 9: corner is not indicated.
  - A-1) 1971 MDOT Control Sec. SS57013, Job #04474A, Sheet 5: 3/4" Pipe
  - A-1) 1976 Wilcox survey, Liber S-1 page 289, Liber S-2 page 147: Fd. 1" Pipe in Mon. Box
  - A-1) 1985 Thomson survey, Liber S-1 page 189, Liber S-2 page 208: Fd. 1" Pipe in Mon. Box

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- A-1) W 1/4 corner, Section 6, T23N, R7W, Fd. 3/4" Pipe in Mon. Box 4.1' South of centerline road to East, 113.7' East of centerline M-66. This corner is accepted as a careful and faithful perpetuation of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-1) Placed Missaukee County Monument on existing corner with #24617

- \*S52°E 63.06 Face clear vision fence post
- \*N64°E 61.51 Face clear vision fence post
- N72°E 137.21 P.Pole
- N28°E 120.38 10" R.Pine

\* = Old witness

Peer Group Reviewed and Approved

Date: 1-2-96  
*J. Dedn Geers*  
J. Dedn Geers, Missaukee Co. Representative

Signed by: *Daniel E. Schripsema* Date: 12-29-95  
Surveyor's Michigan License No. 24617