

JAN 30 1996

# 1030

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKEE COUNTY MICHIGAN

For corners in  
Missaukee  
(County)

Located In: Corner Code #

1. Public Land Survey	T	<u>23</u>	R	<u>7</u>	<u>A-2</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

RECORDED JAN 2 1996 1:15 P.M.

*Debra K. Flere*  
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
6	5	4	3	2	1							
7	8	9	10	11	12							
18	17	16	15	14	13							
19	20	21	22	23	24							
30	29	28	27	26	25							
31	32	33	34	35	36							

I, Daniel E. Schripsema, in a field survey on August, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-2) 1838 GLO
- 1907 Richarson FB #14 page 71, Gas Pipe
- 1967 MDOT Page Set 3/4" pipe
- MDOT Control Sec. 57013, file #57-R-1, Sheet 9: corner is not indicated.
- 1971 MDOT Control Sec. SS57013, Job #04474A, Sheet 5: 3/4" Pipe
- 1973 MDOT Slaminski: 3/4" pipe in Mon Box.
- 1976 Wilcox survey, Liber S-1 page 289, Liber S-2 page 147: Fd. 1" Pipe in Mon. Box
- 1980 Wilcox LCRC, LCRC Liber 1 page 593: Fd. 3/4" Pipe in Mon. Box.
- (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-2) W 1/4 corner, Section 6, T23N, R7W, Fd. 3/4" Pipe in Mon. Box 4.1' South of centerline road to East, 113.7' East of centerline M-66. This corner is accepted as a careful and faithful perpetuation of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-3) Placed Missaukee County Monument on existing corner with #24617

- \*S48°E 77.61 P.Pole
  - \*N69°E 72.90 Fe. Post
  - \*S75°W 77.32 Rd. Sign
  - South 36.20 Set Iron
- \* = Fd. witness nail

Peer Group Reviewed and Approved

Date: 1-2-96  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema* Date 12-29-95

Surveyor's Michigan License No. 24617