

JAN 30 1996

4 1031

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKIEE COUNTY MICHIGAN

For corners in
Missaukee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 23 R 7 A-3
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Section S T R

RECORDED JAN 2 1996 1:15 PM

Carolyn Elrod
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Daniel E. Schripsema, in a field survey on August, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-3) 1838 GLO
- 1895 Richardson Field Book 14 page 49, R.R. Iron
- 1907 Richardson Field Book 14 page 71, Cedar Stake
- Maple stake N90°W 50, Birch Stake N90°E 50
- 1967 MDOT Page: LCRC Liber 1 page 277 Set 1 1/4" Iron Bar in Mon. Box
- 1971 MDOT Control Sec. SS57013, Job # 044741A, Sheet 5
- MDOT File 57-R-1 & 57-R-2, Control Sec. 57013, Sheet 9
- 1994 Schripsema survey: Liber S-3 page 243: LCRC Liber 1 page 277

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-3) SW corner, section 6, T23N, R7W, Fd. 1" Iron Bar in Mon. Box 131.81 East of c.line M-66. This corner is accepted as a careful and faithful reestablishment of the the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-5) Placed Missaukee County Monument on existing corner with #24617

- *N39°E 93.97 14" R.Pine
 - *N28°E 129.26 14" R.Pine
 - S89°E 94.39 8" Poplar
 - S38°E 99.52 12" Poplar
- * = Fd. witness nail

Peer Group Reviewed and Approved

Date: 1-2-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema* Date 12-29-95

Surveyor's Michigan License No. 24617