

JAN 30 1996

1032

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKEE COUNTY MICHIGAN

For corners in Missaukee (County) Located In: _____ Corner Code # _____

1. Public Land Survey T 23 R 7 _____ A-4
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED JAN 2 1996 1:15 Pm
Angela Clark
 REGISTER

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Daniel E. Schripsema, in a field survey on August, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 A-4) 1838 GLO
 1895 Richardson, Field Book 14 page 49: Cedar Stake
 Cedar 30 S77°W 28
 1967 MDOT Page, LCRC Liber 1 page 279: Set 1" Iron Bar
 1971 MDOT Control Sec. SS57013, Job # 044714A Sheet 5
 MDOT File 57-R-1 & 57-R-2, Project 57-27, Sheets 8 & 9.
 1973 MDOT Slaminski witness record: Fd. 1" Bar in Mon. Box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 A-4) W 1/4 corner, Section 7, T23N, R7W, Fd. 1/2" Iron in Mon. Box 119' East of M-66.
 This corner is accepted as a careful and faithful reestablishment of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-4) Place Missaukee County Monument on existing corner with #24617

N34°E 33.51 P.Pole
 S52°E 69.82 8" Cedar
 S75°W 76.34 8" W.Pine
 S16°E 73.72 5" Poplar

Peer Group Reviewed and Approved
 Date: 1-2-96
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema* Date 12-29-95
 Surveyor's Michigan License No. 24617