

1033

JAN 30 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Missaukee (County) Located In: _____ Corner Code # _____

MISSAUKEE COUNTY MICHIGAN

RECORDED JAN 2 1996 1:15 P

Paula E. Geers
REGISTER

- 1. Public Land Survey T 23 R 7 _____ A-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripson, field survey on August, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-5) 1837 GLO post by John Brink, Dep. Surveyor, Hemlock 10 S67°W 16, Hemlock 13 N41°W 60
- A-5) 1895 Richardson survey notes, Fieldbook #14, page 49
- A-5) 1967 Page Gov't Monument Witnesses Record, Liber-page 278: Set 1" Iron Bar
- A-5) 1967 MDOT Page witness record: Set 1" Iron Bar
- A-5) 1971 MDOT Control Sec. SS57013, job #04474A, sheet 4: Found 1" Iron Bar
- A-5) MDOT Slaminski witness record: Found 3/4" pipe
- A-5) MDOT Control Sec. 57013, file #57-R-1 & 57-R-2, sheets 8 & 9: corner is indicated.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-5) Section corner common to Sections 7 and 18
- Found 1" Iron Bar in Mon. Box in centerline of old road bed, and 100' East of centerline of M-66. This corner is accepted as a careful and faithful reestablishment of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-5) Raised existing corner with 1/2" Iron and brass Missaukee County Monument with #24617
- | | | |
|-------|-------|-------------|
| N65°E | 61.72 | 9" Red Pine |
| S72°E | 58.02 | 12" Oak |
| S50°E | 69.23 | 7" Oak |
| S34°E | 78.63 | 6" Poplar |

Peer Group Reviewed and Approved

Date: 1-2-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripson* Date 12-29-95
Surveyor's Michigan License No. 24617