

# 1035

JAN 30 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKEE COUNTY MICHIGAN

For corners in Missaukee (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 23 R 7 \_\_\_\_\_ A-7  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

RECORDED JAN 2 1996 1:15 PM

*[Signature]*  
REGISTER

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Daniel E. Schripsema, in a field survey on August, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-7) 1837 GLO post by John Brink, Deputy Surveyor  
Yellow Pine 22 S21°W 23, Maple 11 N32°W 47
- A-7) 1892-1914 Hastings Notes: Fieldbook #35, page 55
- A-7) 1966 Page Gov't Monument Witnesses Record, Liber-page 250: Found 1" Pipe
- A-7) 1971 MDOT Control Sec. SS57013, job #04474A, sheet 4: Found 1" galvanized iron pipe
- A-7) MDOT Witness sheet: Found 1" pipe  
(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-7) Section corner common to Sections 18 and 19  
  
Found 1" galvanized pipe in Mon. Box in centerline 2-track East and West and old M-66 road bed. This corner is accepted as a careful and faithful perpetuation of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-7) Set 1/2" Iron and brass Missaukee County Monument with #24617  
  

N72°E	58.03	10" Maple
N50°E	80.26	twin 12" Oak
S51°E	65.46	twin 14" Oak
S33°E	79.45	14" Poplar

Peer Group Reviewed and Approved

Date: 1-2-96  
*[Signature]*  
J. Dean Geers, Missaukee Co. Representative

Signed by *[Signature]*

Date 12-29-95

Surveyor's Michigan License No. 24617