

JAN 30 1996

#1036

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKEE COUNTY MICHIGAN

For corners in Missaukee (County) Located In: Corner Code #

- 1. Public Land Survey T 23 R 7 A-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

RECORDED JAN 30 1996 1:45 PM

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell (19, 19) is marked with a dot.

I, Daniel E. Schripsema, in a field survey on August, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
A-8) 1838 GLO post by John Brink, Deputy Surveyor
A-8) 1892-1914 Hastings Notes: Fieldbook #35, page 55
A-8) 1967 Page Gov't Monument Witnesses Record, Liber-page 249: Set 3/4" galvanized iron pipe
A-8) 1971 MDOT Control Sec. SS57013, job #04474A, sheet 4: Found 3/4" galvanized iron pipe
A-8) 1974 Wilcox survey, Liber S-1, page 174
A-8) MDOT Control Sec. 57013, file #57-R-1 & 57-R-2, sheets 8 & 8: corner not indicated.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-8) West 1/4 corner common to Section 19
Found 3/4" galvanized pipe in Mon. Box in centerline of old M-66 road bed. This corner is accepted as a careful and faithful reestablishment of the location of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-8) Set 1/2" Iron and brass Missaukee County Monument with #24617
N66°E 60.10 26" Dead Oak
N45°E 71.98 10" Maple
S86°E 68.97 8" Oak
S42°E 51.69 16" Oak

Peer Group Reviewed and Approved
Date: 1-2-96
J. Dear Geers, Missaukee Co. Representative

Signed by [Signature] Date 12-29-95
Surveyor's Michigan License No. 24617