

JAN 8 0 1996

#1837

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Missaukee Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 23 R 7 \_\_\_\_\_ A-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

MISSAUKEE COUNTY MICHIGAN

RECORDED JAN 2 1996 1115 P

*John Geers*  
REGISTER

Register of Deeds Stamp & File Number

I, Daniel E. Schripsema in a field survey on August, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- A-9) 1838 GLO post by John Brink, Deputy Surveyor  
Beech 10 S66°W 19, White Pine 11 N21°W 30
- A-9) 1892-1912 Hastings Notes: Fieldbook #35, page 54
- A-9) 1892-1914 Hastings Notes: Fieldbook #35, page 55
- A-9) 1966 Page Gov't Monument Witnesses Record, Liber-page 260: Found 5/8" Rerod
- A-9) 1971 MDOT Control Sec. SS57013, job #04474A, sheet 4: Found 1/2" Iron Pipe
- A-9) 1972 Wilcox LCRC, Liber-page 91: Found 1/2" Iron Pipe
- A-9) 1974 Wilcox survey, Liber S-1 page 174
- A-9) MDOT Control Sec. 57013, file #57-R-1 & 57-R-2, sheet 8: corner is not indicated

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-9) Section corner common to Sections 19 and 30

Found 1/2" Iron Pipe in Mon. Box in centerline M-66, and 2.75' South of centerline of M-42. This corner is accepted as a careful and faithful perpetuation of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-9) Set 1/2" Iron and brass Missaukee County Monument with #24617

S63°W	92.83	Guy Pole
N61°E	73.40	Guy Pole
S80°E	32.91	SW Cor. Conc. ROW Mon.
N80°E	60.15	Conc. Mon. w/ brass cap MDOT #57102

Peer Group Reviewed and Approved

Date: 1-2-96  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema* Date 12-29-95

Surveyor's Michigan License No. 24617