

#1038

JAN 8 0 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Missaukee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 23 R 7 A-10
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

MISSAUKEE COUNTY MICHIGAN

RECORDED JAN 2 1996 L115 P

Paula Ebers
REGISTER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema a field survey on August, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- A-10) 1838 GLO post by John Brink, Deputy Surveyor
Yellow Pine 16 S83°W 12, Yellow Pine 16 N22°W 17
 - A-10) 1892-1912 Hastings Notes: Fieldbook #35, page 54
 - A-10) 1966 Page Gov't Monument Witnesses Record, Liber-page 248: Found 5/8" Reinforcing rod
 - A-10) 1981 Wilcox survey, Liber S-2, page 78: Found 5/8" rod
 - A-10) MDOT Control Sec. 57013, file #57-R-1 & 57-R-2, sheets 7-8: corner is not indicated

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- A-10) West 1/4 corner common to Section 30
- Found 5/8" Iron in Mon. Box in centerline of M-66. This corner is accepted as a careful and faithful perpetuation on the original location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-10) Placed Brass Missaukee County Monument on existing corner with #24617

N44°W	81.73	12" twin Cherry
S69°W	51.91	38" Oak
N63°E	66.05	12" Red Pine
S68°E	70.43	24" Oak

Peer Group Reviewed and Approved

Date: 1-2-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by: *Daniel E. Schripsema* Date: 12-29-95
Surveyor's Michigan License No. 24617