

1019

JAN 30 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKEE COUNTY MICHIGAN

For corners in
Missaukee

COMMISSION

Located In:

Corner Code #

RECORDED JAN 2 1996 1:15 PM

Roslyn Flare
REGISTER

- 1. Public Land Survey T 23 R 7 A-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema a field surveyor on August, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-11) 1837 GLO post by John Brink, Deputy Surveyor
White Pine 13 S09°W 31, Yellow Pine 14 N40°W 40
- A-11) 1909 Hastings Notes: Fieldbook #35, page 53
- A-11) 1892-1912 Hastings Notes: Fieldbook #35, page 54
- A-11) 1949 Supervisor's Plat Liber 2 of Plats Page 73
- A-11) 1966 Page Gov't Monument Witnesses Record, Liber-page 246: Found 5/8" Reinforcing rod
- A-11) 1971 MDOT Control Sec. SS57013, job #004474A, sheet #4: Found 5/8" reinf. rod
- A-11) 1972 Wilcox LCRC, Liber-page 92: Fd 5/8" rered
(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-11) Section corner common to Sections 31 and 30

Found 5/8" Iron in Mon. Box 1' East of centerline M-66 and 5' North of centerline Sanborn Rd. This corner is accepted as a careful and faithful perpetuation of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-11) Placed Brass Missaukee County Monument on existing corner with #24617

- *S78°W 105.90 P.Pole
- *S44°E 82.85 10" Spruce
- *N74°E 46.60 P.Pole
- N49°W 136.36 27" Oak
- * = Fd. witness nail

Peer Group Reviewed and Approved

Date: 1-2-96
J. Dean Geers
↓ Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema Date 12-29-95
Surveyor's License No. 24617

