

#1020

JAN 30 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Missaukee

COMMISSION

MISSAUKEE COUNTY MICHIGAN

RECORDED JAN 2 1996 1:15 PM

Carlynn Florie REGISTER

Register of Deeds Stamp & File Number

(County)	Located In:	Corner Code #
1. Public Land Survey	T 23 R 7	A-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema a field survey on August, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-12) 1838 GLO post by John Brink, Deputy Surveyor
Yellow Pine 14 S52°W 2, Yellow Pine 14 N15°W 55
- A-12) 1909 Hastings Notes, Fieldbook #35, pages 53-54
- A-12) 1967 Page Gov't Monument Witnesses Record, Liber-page 238: Found boat spike at Bit. surface of M-66 and on cemetery fence lines.
- A-12) 1977 Wilcox survey, Liber S-1, page 335: Found 3/4" pipe/Mon. Box
- A-12) 1977 Wilcox survey, Liber S-1, page 339: Found 3/4" pipe/Mon. Box
(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-12) West 1/4 corner common to Section 31

Found 1/2" Iron in Mon. Box 3.7' West of centerline M-66. This corner is accepted as a careful and faithful perpetuation of the location of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-12) Placed Brass Missaukee County Monument on existing corner with #24617

S85°W	36.73	15" Spruce
N89°E	38.89	30" Oak
*S34°W	57.42	P.Pole
*N57°E	43.05	P.Pole

* = Fd. witness nail

Peer Group Reviewed and Approved

Date: 1-2-96
J. Dean Geers, Missaukee Co. Representative

Signed by [Signature]

Date 12-29-95

Surveyor's Michigan License No. 24617