

**SURVEY &
REMONUMENTATION**

LIBER 291 PAGE 447

990

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**
Missaukee
(County)

Located In: Corner Code #

1. Public Land Survey	T	23N	7W	D-13
	T			
	T			
	T			
2. Property Controlling in Section	S			
	S			
3. Miscellaneous Property in Sec.	S			
	S			

MISSAUKEE COUNTY MICHIGAN

RECORDED JAN 23 1995 12:02 PM

Paula Flore
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-13) 1853 GLO post by John Brink, Deputy Surveyor
Sugar 8 N 73 W 30, Beech 10 N 16 E 24
- D-13) 1979 J. Wilcox LCRC Liber 1, page 558:
Set railroad spike
N 15 E, 49.85 R.O.W. Marker
N 50 W, 70.19 Tel. Pole
S of W, 74.00 R.O.W. Marker
N 40 E, 88.32 Tel. Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-13) Quarter corner common to Section 32, T23N, R7W and Section 5, T22N, R7W.

Found railroad spike per Liber 1, page 558 and is accepted as a careful and faithful reestablishment of the position of the original corner. Corner is located 16.0' East of centerline of the North-South road and 2.0' North of the centerline of the East-West road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13) Replaced found R.R. Spike with 5/8" Iron and 2 1/2" brass Missaukee County monument and monument box.

- N 46 W 88.06 Tel. Ped. Post
- N 09 E 57.02 P.Pole
- S 11 W 73.94 Top of conc. R.O.W. Marker
- S 22 W 147.52 6" White Pine
- S 12 W 78.91 Capped Iron

Peer Group Reviewed and Approved

Date: 11-2-94
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema Date 12-30-94
Surveyor's Michigan License No. 24617