

**SURVEY &  
REMONUMENTATION**

LIBER 291 PAGE 445

988

APR 24 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**  
**Missaukee**  
(County)

	Located In:		Corner Code #
	23N	7W	F-13
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

MISSAUKEE COUNTY MICHIGAN

RECORDED **JAN 23 1995 12<sup>01</sup> P.M.**

*Paulyn Flare*  
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema, a field surveyor on December, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- F-13) 1853 GLO post by John Brink, Deputy Surveyor
    - White pine 16 N 43 E 7
    - Hemlock 14 N 18 W 17
  - F-13) 1899 County Survey Records
    - W.P.S. 26' S19E 39
    - W.P.S. 18' N12W 40

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- F-13) Quarter corner common to Section 33, T23N, R7W and Sec. 5, T22N, R7W
    - Set corner on line between SE & SW Sec. corners and in line with fence to north. Accepted as the best evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- F-13) Set 5/8" Iron with 2 1/2" brass Missaukee County monument in monument box.

N 64 E	113.78	Telephone pedestal pole
N 07 W	44.27	36" Oak
N 29 W	100.11	10" Oak
N 46 W	95.88	10" Maple

Peer Group Reviewed and Approved  
Date: 12-21-94  
*J. Dear Geers*  
J. Dear Geers, Missaukee Co. Representative

Signed by Daniel E. Schripsema Date 12-30-94  
Surveyor's Michigan License No. 24617

