

1021

JAN 8 0 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MISSAUKEE COUNTY MICHIGAN

For corners in
Missaukee

COMMISSION

RECORDED JAN 2 1996 1:15 P

Barbara Flare
REGISTER

| (County) | Located In: | Corner Code # |
|------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T <u>23</u> R <u>7</u> | K-13 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Daniel E. Schripsema, in a field survey on August, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- K-13) 1838 GLO by John Brink, Deputy Surveyor (Hemlock 28)
 - K-13) 1888 & 1914 E.A. Beathien notes Book 35 page 45 & 58, Cedar stake by Richardson 1888, tel. pole S73W 81 lks
 - K-13) 1958 MSHD M-55 Plan Sheet 10, 57022-S-29-A-3, Fd. Cedar Post 2.1 ft. South of centerline, set Mon. Box
 - K-13) MDOT M-55 file #57-R-1, Control Sec. 57022, sheet 18: indicates corner 2.1 ft. South of centerline M-55
 - K-13) 1990 Geers survey, Liber S-2, page 526: Found Mon. Box
 - K-13) 1995 Schripsema survey, Found Mon. Box.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- K-13) South 1/4 corner Section 36

Found Mon. Box. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-13) Placed 1/2" iron w/ Brass Missaukee County Monument in existing Mon. Box with #24617

| | | |
|-------|-------|---------------------|
| S53°E | 70.62 | Tel. Ped. Post |
| S04°E | 48.52 | Fe. Cor. Post |
| N42°W | 56.64 | MDOT wit Mon. |
| N31°E | 61.00 | Conc. R.O.W. Marker |

Peer Group Reviewed and Approved

Date: 1-2-96
J. Dean Geers
J. Dean Geers, Missaukee Co. Representative

Signed by *Daniel E. Schripsema*
Surveyor's Michigan License No. 24617

Date 12-29-95