

#1022

JAN 30 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

MISSAUKEE COUNTY MICHIGAN

For corners in  
Missaukee

RECORDED JAN 2 1996 1:15 P

*Paula K. Rose*  
REGISTER

(County)	Located in:	Corner Code #
1. Public Land Survey	T <u>23</u> R <u>7</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel E. Schripsema a field surveyor on August, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-13) 1838 GLO post by John Brink, Deputy Surveyor Sugar 8 N78°E 10, Sugar 9 N50°W 30
- L-13) 1888&1914 E.A. Beathien, Co. Surveyor notes Book 35 page 58, Maple 9 N16 1/2W 16 lks.
- L-13) MDOT M-55 file #57-R-1, Control Sec. 57022, sheet 18: corner is not indicated.
- L-13) 1986 Wilcox LCRC, Liber 1 page 709: Found 1 1/4" pipe, raised with iron/cap South 40.93 Fe. Cor., N5°W 68.89 6" Ironwood, N50°W 100.80 14" Maplewood, North 5.5' Centerline M-55
- L-13) 1990 Geers survey, Liber S-2, page 526: Found Iron & cap w/Mon. Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-13) South 1/4 corner common to Section 36

Found 1/2" iron & cap in Mon. Box 5.5' South of centerline M-55, 1.5' West of fence line to the South, and tree line to North. This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13) Placed Brass Missaukee County Monument on existing corner with #24617

N03°E 57.07 4"x4" Post @ Phone Riser  
 S01°W 170.89 P.Pole  
 \*N04°W 68.90 6" Ironwood  
 \*N48°W 100.57 16" Maple  
 \* = Fd. witness nail

Peer Group Reviewed and Approved

Date: 1-2-96  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

Signed By Daniel E. Schripsema Date 12-29-95  
Surveyor's Michigan License No. 24617