

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1185

For corners in
Missaukee
(County)

Located In:

Corner Code #

LIBER 314 PAGE 1266

MISSAUKEE COUNTY MICHIGAN

RECORDED NOV 10 1997 4:30 p.m.

Roslyn Florie
 REGISTER

Register of Deeds Stamp & File Number

- | | | |
|--------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>23N</u> R <u>7W</u> | <u>M-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, J. Dean Geers, in a field survey on June, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-2) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; Sugar 8-N11½W-35; Sugar 8-S40W-25
- M-2) 1892 County Survey Notes; Survey in Section 1, T23N, R7W; Stake and Stone, Maple 16-S26W-83, Corner Fence Post-N87E-48
- M-2) 1911 Beuthien Survey in Section 1, T23N, R7W; Cedar Stake 3x3 and Stone perpetuated from old bearings
- M-2) 1972 L. Cavanagh LCRC, Liber 1, Page 83; Re-survey of Section 6, T23N, R6W; Re-established Corner based on occupation lines; 1/2" Bar-33.0-East, 6" Tri Birch S14W-57.4
- M-2) 1997 DNR LCRC, Liber 1, Page 1120; Found and accepted Iron as recorded in Liber 1, Page 83; S14W -58.37-Tri White Birch, S11E-45.66-10" Tri Maple, East-33.00-Rerod, N58E-27.22-5" Twin Maple, N40W-41.02-4" Cherry, West-33-Carsonite Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-2) Section Corner common to Section 1, T23N, R7W and Section 6, T23N, R6W; Found 1/2" Rerod as recorded in Liber 1, Page 83 and Page 1120. Corner is ± 2' East of centerline trail North-South. This corner is accepted as a careful and faithful re-establishment of the position of the original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-2) Set Missaukee County Monument on existing Iron
 - S15W 58.36 8" Birch clump
 - S10E 45.67 8" Maple clump
 - N61E 27.23 4" Maple clump
 - N42W 41.03 6" Cherry

SURVEY & REMONUMENTATION

JAN 16 1998

SECTION

Peer Group Reviewed and Approved

Date: 10-29-97

J. Dean Geers, Missaukee Co. Representative

Signed by _____

Date 11-6-97

Surveyor's Michigan License No. _____

