

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

#1186  
LIBER 314 PAGE 1267

For corners in

Missaukee Located In: Corner Code #  
(County)

1. Public Land Survey T 23NR 7W M-3  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

MISSAUKEE COUNTY MICHIGAN  
RECORDED NOV 10 1997 4:30 P.M.  
*Carolyn Flare*  
REGISTER  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, J. Dean Geers, in a field survey on June, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- M-3) 1838 GLO Section Post by John Brink, Deputy Surveyor; Beech 9-S14½W-18, Beech 8-N38W-29
  - M-3) 1889 County Survey; perpetuated Corner by driving stake 10" below surface placing a pint bottle on East side of stake and filling around stake with stone.
  - M-3) 1892 County Survey Notes; Survey in Section 1, T23N, R7W; Maple 3-N65W-118
  - M-3) 1895 Richardson Survey in Section 7, T23N, R6W; Stake, Pint Bottle and Stones, Maple-3-N65W-118
  - M-3) 1911 Beuthien Survey in Section 1, T23N, R7W; Corner was used in survey, Maple-3-N65W-118
  - M-3) 1972 L. Cavanagh LCRC, Liber 1, Page 83; re-survey of Section 6, T23N, R6W. Re-established Corner based on occupation lines; Concrete HDWL-N53E-43.68, 3" Cedar-N10W-45.38
- (Continued on back)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- M-3) Section Corner common to Sections 1 and 12, T23N, R7W, and Sections 6 and 7, T23N, R6W; Found 1/2" Rod as recorded in Liber 1, Page 83 and Page 1121. Corner is ± 4' South of centerline East-West road and in centerline road to North. This corner is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3) Set Missaukee County Monument on existing Iron
  - N08W 47.87 8" Cedar
  - N23E 68.23 20" Cherry
  - S15W 32.98 16" Poplar
  - S12E 33.40 6" Poplar


Peer Group Reviewed and Approved

Date: 11-5-97  
*J. Dean Geers*  
J. Dean Geers, Missaukee Co. Representative

SURVEY & REMONUMENTATION

JAN 16 1998

Signed by *J. Dean Geers* SECTION \_\_\_\_\_  
Surveyor's Michigan License No. 33977 No. \_\_\_\_\_ Date 11-6-97



A. Continued

M-3) 1997 DNR LCRC, Liber 1, Page 1121; Found and accepted 1/2" Iron recorded in Liber 1, Page 83; Concrete culvert - N53E-43.68, 7" Cedar-N10W-47.85, 22" White Pine-N77E-99.35, South end concrete culvert-S43E-44.32