

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#1187
 LIBER 314 PAGE 1268

For corners in Missaukee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 23N R 7W _____ M-4
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

MISSAUKEE COUNTY MICHIGAN
 RECORDED NOV 10 1997 4:30 PM
Ruby Klare
 REGISTER
 Register of Deeds Stamp & File Number

I, J. Dean Geers, in a field survey on June, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-4) 1838 GLO Quarter Section Post by John Brink, Deputy Surveyor; Hemlock 10-S82W-34, Sugar 10-N21W-35
- M-4) 1889 County Survey Notes; Perpetuated Corner by driving Hemlock stake 2' long and 3" square level with surface and placing broken china around stake
- M-4) 1895 Richardson Survey in Section 7, T23N, R6W; Stake, Broken Crockery and Stone; No witnesses given
- M-4) 1997 DNR LCRC, Liber 1, Page 1133; Set DNR Monument; Re-established Corner by splitting right-of-way fences to the North and West which seems to represent the most likely location of the original Corner. 3" Red Pine-N55W-53.16, 6" Cherry-S37W-94.41, 14" White Pine-S53E-70.16, Corner Fence Post-N50E-34.72

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-4) Quarter Section Corner common to Section 12, T23N, R7W and Section 7, T23N, R6W. Found DNR Monument as recorded in Liber 1, Page 1133. This Corner is accepted as a careful and faithful re-establishment of the position of the original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-4) Set Missaukee County Monument on existing Iron
 - S35W 94.42 8" Twin Cherry
 - N56W 53.21 5" Red Pine
 - N50E 34.57 Corner Fence Post
 - S53E 70.10 14" White Pine


SURVEY & REMONUMENTATION

Peer Group Reviewed and Approved

Date: 11-5-97
J. Dean Geers
 J. Dean Geers, Missaukee Co. Representative

JAN 16 1998

Signed by _____
 Surveyor's Michigan License No. 33877



Date 11-6-97